













# Boat Harbor Treatment Plant




Photo Credit: VDOT



**Legend**

-  **Boat Harbor Treatment Plant**
-  **CIP Interceptor Point**
-  **CIP Pump Station Point**
-  **CIP Interceptor Line**
-  **CIP Abandonment**
-  **Treatment Plant Service Area**
-  **HRSD Interceptor Force Main**
-  **HRSD Interceptor Gravity Main**
-  **HRSD Treatment Plant**
-  **HRSD Pressure Reducing Station**
-  **HRSD Pump Station**



**Boat Harbor Treatment Plant Service Area  
CIP Projects**

**Treatment Plant Projects**


- BH015300**
- BH015700**
- BH015710**
- BH015720**



**CIP Location**



Service Area




**BHO 13020**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



**BHO 13020**

**Willard Avenue Pump Station Replacement**

N  
W E  
S

**CIP Location**

Hampton



System: Boat Harbor  
Type: Pump Stations

Driver Category: Capacity Improvements  
Project Status: Design  
Regulatory: None

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$9,991	\$637	\$3,748	\$5,601	\$5	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project includes the replacement of the Willard Avenue Pump Station (PS) to address conditional issues. The proposed replacement will include a relocated pump station and new gravity and force main connections to the existing systems.

**PROJECT JUSTIFICATION**

This project will improve pump station capacity for the service area and reduce operation and maintenance demands. The existing Willard Avenue Pump Station is located at 219 National Avenue in Hampton, Virginia. The Station serves portions of Buckroe, Woodland and Phoebus including Fort Monroe and receives flow from multiple City Pump Stations and the HRSD Bay Shore Lane Pump Station. Flows can be diverted from the York River WWTP collection system to the Willard Avenue Pump Station through a valved connection at the HRSD Woodland Road Pump Station. The station discharges flows through a 30-inch force main to a gravity sewer manhole in downtown Hampton. A new force main is planned to realign the Hampton Trunk Sewer Extension Divisions I & J Phase II to remove the pipeline from the Hampton University campus. A new pump station will accommodate a wide range of wet weather flows as well as offer operational flexibility during dry weather periods. The following items are justification for completing this project: The existing pump station was constructed in 1944. At 75 years old, it is nearing the end of its anticipated useful life. The existing pump station parcel is only 0.14 acres, which does not allow for any expansion and does not meet our current parcel size standards for a new pump stations site. Furthermore, building a new pump station at this location will be challenging given the close proximity to residents. HRSD will need to acquire a new parcel in the vicinity of the existing PS to build a new one. Upon completion of the new PS, the existing PS will be demolished and the parcel transferred or sold.

**FUNDING TYPE**

Funding Type: Clean Water Proposed

**CONTACTS**

Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Eddie Abisaab  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	01/01/2019
PER	05/02/2019
Design Delay	10/01/2019
Design	10/02/2019
Bid Delay	08/01/2020
PreConstruction	08/01/2020
Construction	11/01/2020
Closeout	07/01/2022

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 3</b>
PrePlanning	\$2,000
PER	\$102,440
Design	\$536,026
PreConstruction	\$5,000
Construction	\$9,340,653
Closeout	\$5,000
<b>Est. Program Cost</b>	<b>\$9,991,119</b>
Contingency Budget	\$1,868,131
<b>Est. Project Costs</b>	<b>\$11,859,250</b>




**BHO14000**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



**BHO 14000**

**West Avenue and 35th Street  
Interceptor Force Main  
Replacement**

N  
W E  
S

**CIP Location**

Newport News



**West Avenue and 35th Street Interceptor Force Main Replacement**

**PR\_BH014000**

System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: Proposed  
Regulatory: Rehab Plan Phase Two

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$3,665	\$38	\$265	\$1,108	\$2,252	\$3	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project will replace approximately 3,750 linear feet (LF) of cast iron force main, primarily along West Avenue and 35th Street in the City of Newport News. Approximately 1,000 ft of the force main is 20-inch, 250 ft is 18-inch, and 2,500 ft is 12-inch pipe.

**PROJECT JUSTIFICATION**

North Shore Operations has experienced six breaks on this line. Two occurred in the late 1990's, one occurred in 2008, two occurred in late 2010, and the most recent break was in early 2013. The breaks have occurred due to a variety of reasons, the two in 2010 occurred due to multiple stress fractures along the crown and a circumferential crack, respectively. The most recent break (2013) was also a stress fracture that occurred between the spring line and crown of the pipe.

In addition to the poor track record that North Shore Operations has on this pipe, it should be noted that this force main is a cast iron (CI) pipe that was installed in the 1940's. CI is a brittle material that is susceptible to soil settlement and local loading that sometimes leads to localized longitudinal failures.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Sam McAdoe  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	01/01/2020
PER	04/01/2020
Design Delay	11/01/2020
Design	11/01/2020
Bid Delay	10/01/2021
PreConstruction	10/01/2021
Construction	02/01/2022
Closeout	06/01/2023

**COST ESTIMATE**

Cost Estimate Class:	Class 5
PrePlanning	\$0
PER	\$88,346
Design	\$294,430
PreConstruction	\$5,000
Construction	\$3,272,017
Closeout	\$5,000
<b>Est. Program Cost</b>	<b>\$3,664,793</b>
Contingency Budget	\$818,005
<b>Est. Project Costs</b>	<b>\$4,482,798</b>



**BHO14220**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station

Feet

0    395    790    1,580    2,370    3,160

## BHO 14220

### Hampton Trunk Sewer Extension Divisions I and J Relocation Phase II

**CIP Location**

Hampton



System: Boat Harbor  
Type: Pipelines

Driver Category: Relocation  
Project Status: Design  
Regulatory: None

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$15,540	\$1,048	\$6,300	\$7,548	\$644	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project includes the replacement of 7,500 linear feet (LF) of 30-inch force main (FM) from the new Willard Avenue Pump Station (PS) with 6,800 LF of new 24-inch FM. The new force main will originate from the new Willard Ave PS to the connection at E. Queen Street and Eaton Street. The location of the new Willard Ave PS is still pending and may impact the alignment of the FM. The following ancillary work will be required as part of this project:  
A 600 LF extension of the 10-inch FM from City of Hampton PS 003.  
A 1000 LF relocation of the 4-inch FM from the privately owned Hampton Harbor PS.  
Conveyance of Hampton University PS (Sta. #211) to Hampton University or the Veteran Affairs Medical Center.

**PROJECT JUSTIFICATION**

In combination with CIP BH014210, this project will address critical areas within the City of Hampton with significant wet weather capacity issues as identified in the Hampton Study completed by Brown and Caldwell (BC). The Hampton Study was a collaborative effort between BC, the City of Hampton and HRSD to identify, evaluate, and select the preferred alternatives to address the identified capacity issues. The existing Willard Avenue PS 30-inch discharge FM was originally installed in the 1945-46 timeframe, with a portion of the main relocated in 1956 as part of the Interstate-64 (I-64) project. Given the age of this line, the documented failure near the I-64 sound wall, limited diversion options, its depth in the vicinity of the interstate off ramp, and Hampton University's request for HRSD to abandon this pipe, replacement is necessary.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Eddie Abisaab  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning 05/01/2015  
PER 01/01/2016  
Design Delay 07/01/2016  
Design 07/01/2018  
Bid Delay 06/01/2020  
PreConstruction 06/01/2020  
Construction 09/01/2020  
Closeout 08/01/2022

**COST ESTIMATE**

**Cost Estimate Class: Class 2**  
PrePlanning \$1,462  
PER \$85,020  
Design \$956,800  
PreConstruction \$15,000  
Construction \$14,466,926  
Closeout \$15,000  
**Est. Program Cost \$15,540,208**  
**Contingency Budget \$2,893,385**  
**Est. Project Costs \$18,433,593**



**BHO14500**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station

Feet

0 155 310 620 930 1,240

## BHO 14500

### Ivy Home-Shell Road Sewer Extension Division I Replacement

N  
W E  
S

**CIP Location**

Hampton



**Ivy Home-Shell Road Sewer Extension Division I  
Replacement**

**PR\_BH014500**

System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: PER  
Regulatory: Rehab Plan Phase Two

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$2,088	\$74	\$16	\$585	\$1,414	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project will involve diversion of the LaSalle Avenue Sanitary Sewer Force Main (NF-085) in the City of Hampton from the current discharge manhole at the intersection of LaSalle Avenue to Shell Road to an alternative downstream manhole at the intersection of Victoria Boulevard and Ivy Home Road. This diversion would significantly reduce the hydraulic grade line (HGL) in the HRSD gravity sewer and address the capacity concern identified in the regional hydraulic model. The Preliminary Engineering Report (PER) for this project found that abandonment and replacement of the existing HRSD gravity sewer was not feasible due to conflicts with storm sewers and other utilities along the replacement corridor. This project should be coordinated with the Regional Wet Weather Master Plan. Manholes in the Ivy Home-Shell Road area that were identified for rehabilitation under Phase 2 of the rehab plan were removed from the scope of this project and included in GN012130.

**PROJECT JUSTIFICATION**

This project will address critical areas within the City of Hampton with significant wet weather capacity issues as identified in the Hampton Study completed by Brown and Caldwell (BC). This project should be coordinated with the Regional Wet Weather Master Plan. The Hampton Study was a collaborative effort between BC, the City of Hampton and HRSD to identify, evaluate and select the preferred alternatives to address the identified capacity issues. The gravity reroute to 001-PS was identified as the preferred alternative (Alternative 1B) for the Ivy Home Road/Chesapeake Avenue area. This alternative includes increasing the size of the main gravity pipe discharging into the Victoria Boulevard Pump Station (PS), thus, increasing sewer capacity for that service area. The increased capacity of this line, combined with the modifications rerouting flow from the Ivy Home Road sewer to the Victoria Boulevard PS, will facilitate capacity improvements to the Chesapeake Avenue gravity sewer (Alternative 2A - Pump Station and Force Main).

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Phil Hughes  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	05/01/2015
PER	01/01/2016
Design Delay	06/01/2016
Design	06/01/2021
Bid Delay	02/01/2022
PreConstruction	02/01/2022
Construction	04/01/2022
Closeout	04/01/2023

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 5</b>
PrePlanning	\$689
PER	\$73,329
Design	\$125,775
PreConstruction	\$5,000
Construction	\$1,878,240
Closeout	\$5,000
<b>Est. Program Cost</b>	<b>\$2,088,033</b>
Contingency Budget	\$155,856
<b>Est. Project Costs</b>	<b>\$2,243,889</b>




**BHO14600**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



# BHO 14600

## 46th Street Diversion Sewer Rehabilitation Replacement

**CIP Location**

Hampton



System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: Design  
Regulatory: Rehab Plan Phase Two

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$11,791	\$1,044	\$3,111	\$7,039	\$597	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

This project will involve the rehabilitation and/or replacement of the main sanitary sewer trunk line on Newport News Shipbuilding property. The timing of these infrastructure improvements will need to be sequenced with the Newport News Shipyard (NNS) in accordance with an agreement to be drafted and executed prior to the construction phase. This project will include the installation of a new main sanitary sewer trunk line in the City right-of-way outside of NNS property, which will divert public flow from the sewer trunk line on NNS property.

## PROJECT JUSTIFICATION

This project will address long standing conditional, access, encroachment, and jurisdictional issues related to the James River Diversion Sewer - 46th Street constructed in 1945 under the Federal Works Agency, Docket No. VA 44-264. Responsibility for maintenance and operation was assigned to HRSD in 1950 with an expiration of responsibilities in 1979 according to the easement granted to the United States of America by the City of Newport News and subsequently assigned to HRSD. Upon expiration of the easement in 1979, responsibility for maintenance and operation of the gravity line has been in question. Prior to a complete Condition Assessment report prepared by Whitman, Requardt and Associates (WRA) in June 2011, several studies of the existing system have been prepared by consultants hired by Newport News Shipyard, all detailing limited system capacity, numerous deficiencies and missing infrastructure related to building/storage area construction.

## FUNDING TYPE

Funding Type: Clean Water Proposed

## CONTACTS

Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Eddie Abisaab  
Contacts-Managing Dept: Engineering

## PROPOSED SCHEDULE START DATE

PrePlanning 01/01/2017  
PER 01/01/2018  
Design Delay 03/01/2019  
Design 03/01/2019  
Bid Delay 09/01/2020  
PreConstruction 09/01/2020  
Construction 02/01/2021  
Closeout 08/01/2022

## COST ESTIMATE

**Cost Estimate Class: Class 4**  
PrePlanning \$1,626  
PER \$278,752  
Design \$932,560  
PreConstruction \$10,000  
Construction \$10,558,500  
Closeout \$10,000  
**Est. Program Cost \$11,791,438**  
Contingency Budget \$2,111,700  
**Est. Project Costs \$13,903,138**




**BHO14700**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



## BHO 14700

### Boat Harbor Outlet Sewer Improvements

**CIP Location**

Newport News



System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: Construction  
Regulatory: Rehab Plan Phase One

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$6,000	\$2,518	\$3,483	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project will rehabilitate or replace approximately 3,500 linear feet of gravity pipeline and associated manholes. Pipe diameters range from 48 to 54-inches. Project extends from MH-NG-169-852 to MH-NG-169-1395 and from MH-NG-169-3984 to MH-NG-124-5328. Rehabilitation work includes the 26th Street siphons and the associated chambers. The 25th Street siphons and associated chambers were rehabilitated under a prompt repair contract.

**PROJECT JUSTIFICATION**

Condition assessment activities indicate that these assets present a material risk of failure due to physical condition defects.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**

Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Phil Hughes  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	02/01/2017
PER	01/01/2018
Design Delay	06/01/2018
Design	06/01/2018
Bid Delay	04/01/2019
PreConstruction	08/01/2019
Construction	12/01/2019
Closeout	03/01/2021

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 1</b>
PrePlanning	\$1,496
PER	\$87,700
Design	\$241,035
PreConstruction	\$13,340
Construction	\$5,651,879
Closeout	\$5,000
<b>Est. Program Cost</b>	<b>\$6,000,450</b>
Contingency Budget	\$524,461
<b>Est. Project Costs</b>	<b>\$6,524,911</b>




**BHO14800**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



## BHO 14800

### Jefferson Avenue Extension Gravity Improvements

**CIP Location**

Newport News



System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: Construction  
Regulatory: Rehab Plan Phase One

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$2,872	\$2,431	\$441	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project is to rehabilitate and/or replace 4800 linear feet of gravity pipeline and associated manholes. Pipe diameters range from 27 to 36-inches. Project extends from MH-NG-103-2020 to MH-NG-106-8070 and from MH-NG-108-2800 to MH-NG-108-2340. Manholes MH-NG-108-719 and MH-NG-112-12636 are also included.

**PROJECT JUSTIFICATION**

Condition assessment activities indicate that these assets present a material risk of failure due to I/I.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Phil Hughes  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	05/01/2016
PER	02/01/2017
Design Delay	06/01/2017
Design	07/01/2017
Bid Delay	12/01/2018
PreConstruction	12/01/2018
Construction	09/01/2019
Closeout	08/01/2020

**COST ESTIMATE**

Cost Estimate Class:	Class 1
PrePlanning	\$0
PER	\$52,467
Design	\$189,969
PreConstruction	\$10,727
Construction	\$2,613,674
Closeout	\$5,000
<b>Est. Program Cost</b>	<b>\$2,871,836</b>
Contingency Budget	\$522,734
<b>Est. Project Costs</b>	<b>\$3,394,571</b>




**BHO 14900**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



## BHO 14900

### Hampton Trunk Sewer Extension Division K Gravity Improvements

**CIP Location**

Hampton



System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: PER  
Regulatory: Rehab Plan Phase Two

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$4,498	\$172	\$748	\$3,573	\$5	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project is to rehabilitate and/or replace 3700 linear feet of gravity pipeline with associated manholes. Pipe diameter is 30-inches. Project extends from MH-NG-160-25773 to NS-PS-225-1. There is also a point repair required between MH-NG-160-26350 and MH-NG-160-26040.

**PROJECT JUSTIFICATION**

Condition assessment activities indicate that these assets present a material risk of failure due to I/I.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Eddie Abisaab  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning 08/01/2019  
PER 09/01/2019  
Design Delay 04/01/2020  
Design 04/01/2020  
Bid Delay 02/01/2021  
PreConstruction 02/01/2021  
Construction 05/01/2021  
Closeout 07/01/2022

**COST ESTIMATE**

**Cost Estimate Class: Class 4**  
PrePlanning \$0  
PER \$108,706  
Design \$210,860  
PreConstruction \$5,000  
Construction \$4,168,100  
Closeout \$5,000  
**Est. Program Cost \$4,497,666**  
Contingency Budget \$833,620  
**Est. Project Costs \$5,331,286**




**BHO15000**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



## BHO 15000

### Orcutt Avenue and Mercury Blvd Gravity Sewer Improvements

**CIP Location**

Newport News



# Orcutt Avenue and Mercury Blvd Gravity Sewer Improvements

PR\_BH015000

System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: Construction  
Regulatory: Rehab Plan Phase One

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$8,963	\$8,959	\$4	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

## PROJECT DESCRIPTION

- Orcutt Avenue Section A Gravity Sewer Rehabilitation - 7,220 linear feet (LF) of gravity pipeline and 42 manholes are referred for action. Pipe diameters range from 15 to 18-inches. Project extents are from MH-NG-051-6116 to MH-NG-127-3791. Upsizing the Mercury Boulevard/Orcutt Avenue crossing from a 24-inch to a 36-inch. Upsizing roughly 300 LF of pipe on Mercury Blvd from an 18-inch to a 30-inch.

- Mercury Boulevard Gravity Sewer Rehabilitation - 9,400 LF of gravity pipeline and 39 manholes are referred for action. Pipe diameters range from 15 to 18-inches. Project extents are from MH-NG-057-6293 to MH-NG-127-3791. City of Hampton sanitary sewer infrastructure rehabilitation work will also be included in this project. A Cost Sharing Agreement was executed to cover the cost of this work.

## PROJECT JUSTIFICATION

Condition assessment activities indicate that these assets present a material risk of failure due to I/I and physical condition defects.

## FUNDING TYPE

Funding Type: Clean Water Approved

## CONTACTS

Contacts-Requesting Dept: Compliance Assurance  
 Contacts-Dept Contacts: Eddie Abisaab  
 Contacts-Managing Dept: Engineering

## PROPOSED SCHEDULE START DATE

PrePlanning 02/01/2013  
 PER 12/02/2013  
 Design Delay 04/01/2014  
 Design 04/01/2014  
 Bid Delay 03/01/2016  
 PreConstruction 04/01/2018  
 Construction 08/01/2018  
 Closeout 04/01/2020

## COST ESTIMATE

**Cost Estimate Class: Class 1**  
 PrePlanning \$0  
 PER \$68,124  
 Design \$581,596  
 PreConstruction \$8,439  
 Construction \$8,289,554  
 Closeout \$15,000  
**Est. Program Cost \$8,962,713**  
 Contingency Budget \$414,478  
**Est. Project Costs \$9,377,191**




**BHO 15300**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



**BHO 15300**

**Boat Harbor Treatment Plant  
Switchgear and Controls  
Replacements**



**CIP Location**



Hampton



**Boat Harbor Treatment Plant Switchgear and Controls Replacements**

**PR\_BH015300**

System: Boat Harbor  
Type: Electrical

Driver Category: Aging Infrastructure/Rehabilitation  
Project Status: Construction  
Regulatory: None

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$8,954	\$7,231	\$1,723	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project is to design and construct needed replacement of the treatment plant main switchgear, generator switchgear, controls and appurtenances. The replacement of the main plant switchgear will require the construction of new building. The work also includes flood mitigation for sub-station 1 & 2.

**PROJECT JUSTIFICATION**

This project will replace 35 year old switchgear, which are nearing the end of their useful life. The main and generator switchgear is starting to become unreliable. The breaker racking and closing mechanisms have alignment issues and breakers as well as switches have failed to open and/or close due to fatigue of parts. Replacement parts are becoming difficult to obtain. New buildings (main switchgear and emergency switchgear) are required to house the switchgear due to the limited available space on the plant site and the need to maintain plant operations during construction.

**FUNDING TYPE**

Funding Type: Clean Water Approved

**CONTACTS**


Contacts-Requesting Dept: Operations-Treatment  
Contacts-Dept Contacts: Eddie Abisaab  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	09/01/2013
PER	09/01/2013
Design Delay	03/01/2014
Design	09/01/2014
Bid Delay	10/01/2015
PreConstruction	06/01/2018
Construction	04/01/2019
Closeout	10/01/2020

**COST ESTIMATE**

Cost Estimate Class:	Class 1
PrePlanning	\$0
PER	\$79,465
Design	\$929,136
PreConstruction	\$17,905
Construction	\$7,912,192
Closeout	\$15,000
<b>Est. Program Cost</b>	<b>\$8,953,698</b>
<b>Contingency Budget</b>	<b>\$689,306</b>
<b>Est. Project Costs</b>	<b>\$9,643,004</b>




**BHO 1550**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



**BHO 1550**

**LaSalle Avenue Interceptor Force  
Main Replacement**

N  
W E  
S

**CIP Location**

Hampton



System: Boat Harbor  
Type: Pipelines

Driver Category: Aging Infrastructure/Rehabilitation  
Project Status: Proposed  
Regulatory: None

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$1,920	\$0	\$0	\$0	\$0	\$83	\$1,144	\$692	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project involves the replacement of approximately 3,250 linear feet of 14-inch Cast Iron (CI) pipe from the C&O Railroad tracks and Pembroke Avenue to HRSD's terminal manhole, MH-142-4110, at the intersection of LaSalle Avenue and Shell Road.

**PROJECT JUSTIFICATION**

This project will replace the existing 14-inch CI force main from approximately station 120+00 to station 152+50. The original LaSalle Avenue Sanitary Sewer Force Main was installed in 1957 as 14-inch CI pipe. This force main extends from the east side of I-64 from the newly constructed Freeman Drive Pump Station and travels southward down LaSalle Avenue to its terminus at HRSD's MH-142-4110 at the intersection of LaSalle Avenue and Shell Road in Hampton. During the installation of new natural gas service lines to residents along LaSalle Avenue, Virginia Natural Gas' contractor exposed HRSD's 14-inch CI line to verify clearance. Upon excavation and uncovering HRSD's force main, it was observed that this line was corroded to the point of failure. As HRSD's crews worked to repair this line, further holes in the force main developed due to extremely frail pipe wall conditions. The hydraulic conditions of this force main are such that severe internal hydrogen sulfide (H2S) corrosion is likely. There are no air vents on pipe between stations 134+50 and 152+50 and the profile of this line dictate that it does not run full. As such, it is anticipated that vast majority of this line from station 134+50 to station 152+50, is in similar deteriorated condition as experienced during the emergency repair of our line. Similarly, there is another unvented high spot at station 122+50, between the C&O Railroad tracks and Pembroke Avenue. The complete replacement of this section of pipe is warranted due to conditional threats.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Sam McAdoo  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	01/01/2024
PER	02/01/2024
Design Delay	06/01/2024
Design	06/01/2024
Bid Delay	12/01/2024
PreConstruction	12/01/2024
Construction	01/01/2025
Closeout	11/01/2025

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 5</b>
PrePlanning	\$0
PER	\$61,759
Design	\$130,115
PreConstruction	\$5,000
Construction	\$1,717,953
Closeout	\$5,000
<b>Est. Program Cost</b>	<b>\$1,919,827</b>
Contingency Budget	\$429,488
<b>Est. Project Costs</b>	<b>\$2,349,315</b>



**BHO15600**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station

Feet

0    360    720    1,440    2,160    2,880

## BHO 15600

### Hampton Trunk A and B Replacement-Jefferson Avenue to Walnut Avenue

N  
W    E  
S

**CIP Location**

Hampton



**Hampton Trunk A and B Replacement - Jefferson Avenue to Walnut Avenue**

PR\_BH015600

System: Boat Harbor  
Type: Pipelines

Driver Category: Aging Infrastructure/Rehabilitation  
Project Status: Design  
Regulatory: None

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$16,803	\$1,682	\$10,667	\$4,454	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project involves the replacement of approximately 5,000 linear feet (LF) of 36-inch Ductile Iron (DI) and 4,800 LF of 36-inch/34-inch Reinforced Concrete Pressure (RCP) pipe from just north of the intersection of 14th Street and Jefferson Avenue to the intersection of 16th Street and Walnut Avenue. This project will replace the existing force main from the upstream terminus of the Hampton Trunk 'A' Replacement project to the downstream terminus of the Hampton Trunk 'B' – Claremont FM project.

**PROJECT JUSTIFICATION**

The original Hampton Trunk 'A' and 'B' sections were installed in 1944 as part of the Federal Works Agency projects. This infrastructure was originally installed as 48-inch, 36-inch, and 34-inch RCP gravity pipe and force main pipe from Claremont Avenue Pump Station to Boat Harbor Treatment Plant. In 1991, the 48-inch RCP gravity sewer and a portion of the 36-inch RCP force main was replaced with 42-inch Ductile Iron Pipe (DIP) gravity and 36-inch DIP force main. During the recent Hampton Trunk 'A' Replacement project, the joints of the removed 36-inch DIP force main were found to be severely corroded. An analysis was performed and determined that the interior lining delaminated and failed, resulting in severe hydrogen sulfide (H2S) corrosion of the ductile iron pipe. Additionally, visual inspection of the connection point found delaminated interior lining at the joint requiring Ultrasonic Thickness (UST) testing to determine an adequate point of connection. Hydraulic analysis performed on Hampton Trunk 'A' and 'B' indicate that the system operates at less than full flow during dry weather. Smart Ball inspection performed for the Condition Assessment Program also revealed the presence of gasses and/or air. The dry weather hydraulic conditions in this part of the system dictate that a significant tail water condition is present and reaches a great distance upstream from where the force main discharges to gravity. This head space condition in the force main significantly increases the potential for H2S corrosion. These system flow characteristics and delaminated joints significantly increase the potential for additional future failures.

**FUNDING TYPE**

Funding Type: Clean Water Proposed

**CONTACTS**

Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Matt Poe  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	02/01/2018
PER	07/01/2018
Design Delay	03/01/2019
Design	03/01/2019
Bid Delay	03/01/2020
PreConstruction	03/01/2020
Construction	06/01/2020
Closeout	12/01/2021

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 1</b>
PrePlanning	\$1,509
PER	\$181,699
Design	\$600,000
PreConstruction	\$10,000
Construction	\$16,000,000
Closeout	\$10,000
<b>Est. Program Cost</b>	<b>\$16,803,208</b>
Contingency Budget	\$2,400,000
<b>Est. Project Costs</b>	<b>\$19,203,208</b>




**BHO 15700**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



## BHO 15700

### Boat Harbor Treatment Plant Pump Station Conversion

**CIP Location**

Newport News



System: Boat Harbor  
Type: SWIFT

Driver Category: Nutrient Reduction  
Project Status: Proposed  
Regulatory: Integrated Plan-SWIFT

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$62,266	\$155	\$926	\$2,241	\$556	\$18,760	\$38,778	\$850	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

The Boat Harbor Treatment Plant will be converted to a pumping station, including equalization and headworks facilities while remaining in operation for wastewater treatment during conversion. The new infrastructure will be designed to meet HRSD's resiliency standards and consider remote operation and access in future conditions including sea level rise.

**PROJECT JUSTIFICATION**

The James River Waste Load Allocation (WLA) requires HRSD to continue reducing the mass of nutrients discharged from associated treatment plant outfalls. The planned reduction of nutrients is largely completed through implementation of the SWIFT program. The SWIFT master planning effort has determined that advanced water treatment and injection at Boat Harbor has significant physical limitations including site availability and resiliency to sea level rise. In addition, a financial analysis indicates there is significant long term cost savings associated with consolidating wastewater treatment and SWIFT facilities at Nansmond Treatment Plant. This project will allow HRSD to further reduce the amount of nutrients contributed to the James River basin. Upgrades to Nansmond Treatment Plant to accommodate the additional flow will be completed under a separate capital project.

**FUNDING TYPE**

Funding Type: WIFIA

**CONTACTS**

Contacts-Requesting Dept: Engineering  
Contacts-Dept Contacts: Lauren Zuravnsky  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning 07/01/2021  
PER 11/01/2021  
Design Delay 07/01/2022  
Design 09/01/2021  
Bid Delay 07/01/2022  
PreConstruction 01/01/2022  
Construction 07/01/2022  
Closeout 01/01/2025

**COST ESTIMATE**

**Cost Estimate Class: Class 5**  
PrePlanning \$0  
PER \$1,069,856  
Design \$2,747,871  
PreConstruction \$61,135  
Construction \$58,386,771  
Closeout \$0  
**Est. Program Cost \$62,265,633**  
Contingency Budget \$12,453,127  
**Est. Project Costs \$74,718,760**




**BHO15710**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



**BHO 15710**

**Boat Harbor Treatment Plant  
Transmission Force Main Section 1  
(Subaqueous)**

**CIP Location**

Hampton



**Boat Harbor Treatment Plant Transmission Force Main  
Section 1 (Subaqueous)**

**PR\_BH015710**

System: Boat Harbor  
Type: SWIFT

Driver Category: Nutrient Reduction  
Project Status: Proposed  
Regulatory: Integrated Plan-SWIFT

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$65,649	\$0	\$947	\$594	\$4,094	\$30,196	\$29,818	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

The project consists of the subaqueous crossing of the James River to convey flow to the Nansemond Treatment Plant. This project is anticipated to be delivered by the design-build procurement method due to the unique construction techniques required and coordination of construction schedule and permit requirements.

**PROJECT JUSTIFICATION**

The James River Waste Load Allocation (WLA) requires HRSD to continue reducing the mass of nutrients discharged from associated treatment plant outfalls. The planned reduction of nutrients is largely completed through implementation of the SWIFT program. The SWIFT master planning effort has determined that advanced water treatment and injection at Boat Harbor has significant physical limitations including site availability and resiliency to sea level rise. In addition, a financial analysis indicates there is significant long term cost savings associated with consolidating wastewater treatment and SWIFT facilities at Nansemond Treatment Plant. This project will allow HRSD to further reduce the amount of nutrients contributed to the James River basin. Upgrades to Nansemond Treatment Plant to accommodate the additional flow will be completed under a separate capital project.

**FUNDING TYPE**

Funding Type: WIFIA

**CONTACTS**


Contacts-Requesting Dept: Engineering  
Contacts-Dept Contacts: Lauren Zuravnsky  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning 02/01/2020  
PER 02/01/2020  
Design Delay 02/01/2021  
Design 06/01/2020  
Bid Delay 02/01/2021  
PreConstruction 08/01/2020  
Construction 04/01/2021  
Closeout 06/01/2023

**COST ESTIMATE**

**Cost Estimate Class: Class 5**  
PrePlanning \$0  
PER \$1,127,990  
Design \$4,774,560  
PreConstruction \$64,457  
Construction \$59,681,992  
Closeout \$0  
**Est. Program Cost \$65,648,999**  
Contingency Budget \$13,129,800  
**Est. Project Costs \$78,778,799**




**BHO15720**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



**BHO 15720**

**Boat Harbor Treatment Plant  
Transmission Force Main Section 2  
(Land)**

N  
W — E  
S

**CIP Location**

Hampton



**Boat Harbor Treatment Plant Transmission Force Main  
Section 2 (Land)**

PR\_BH015720

System: Boat Harbor  
Type: SWIFT

Driver Category: Nutrient Reduction  
Project Status: Proposed  
Regulatory: Integrated Plan-SWIFT

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$16,412	\$0	\$282	\$1,060	\$150	\$3,656	\$11,264	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

The project consists of the on-land connection of Section 1 to the Nansemond Treatment Plant. This project is generally a standard Interceptor Force Main (IFM) utilizing open cut and a Horizontal Direction Drill (HDD) crossing of I-664. This project is anticipated to be delivered by the design-bid-build procurement method due to the standard construction methods required. HRSD desires to construct this section of the IFM soon to accommodate development of the Tidewater Community College (TCC) property.

**PROJECT JUSTIFICATION**

The James River Waste Load Allocation (WLA) requires HRSD to continue reducing the mass of nutrients discharged from associated treatment plant outfalls. The planned reduction of nutrients is largely completed through implementation of the SWIFT program. The SWIFT master planning effort has determined that advanced water treatment and injection at Boat Harbor has significant physical limitations including site availability and resiliency to sea level rise. In addition, a financial analysis indicates there is significant long term cost savings associated with consolidating wastewater treatment and SWIFT facilities at Nansemond Treatment Plant. This project will allow HRSD to further reduce the amount of nutrients contributed to the James River basin. Upgrades to Nansemond Treatment Plant to accommodate the additional flow will be completed under a separate capital project.

**FUNDING TYPE**

Funding Type: WIFIA

**CONTACTS**


Contacts-Requesting Dept: Engineering  
Contacts-Dept Contacts: Lauren Zuravnsky  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**


PrePlanning 02/01/2020  
PER 02/01/2020  
Design Delay 02/01/2021  
Design 06/01/2020  
Bid Delay 02/01/2021  
PreConstruction 08/01/2020  
Construction 04/01/2021  
Closeout 06/01/2023

**COST ESTIMATE**

**Cost Estimate Class: Class 5**  
PrePlanning \$0  
PER \$281,997  
Design \$1,193,640  
PreConstruction \$16,114  
Construction \$14,920,498  
Closeout \$0  
**Est. Program Cost \$16,412,249**  
Contingency Budget \$3,282,450  
**Est. Project Costs \$19,694,699**




- BHO 15801**
- Project Interceptor Line
  - Project Interceptor Point
  - Project Pump Station Point
  - Project Area
- Legend**
- CIP Interceptor Point
  - CIP Pump Station Point
  - CIP Interceptor Line
  - CIP Abandonment
  - CIP Project Area
  - HRSD Interceptor Force Main
  - HRSD Interceptor Gravity Main
  - HRSD Treatment Plant
  - HRSD Pressure Reducing Station
  - HRSD Pump Station



**BHO 15801**

**14th Street Offline Storage (BH-HPP-01A)**





System: Boat Harbor  
Type: Offline Storage

Driver Category: I&I Abatement-IP/RWWMP  
Project Status: Proposed  
Regulatory: Integrated Plan-HPP

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$14,828	\$0	\$0	\$0	\$868	\$822	\$8,260	\$4,878	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project will install a new 4.3 million gallon (MG) storage tank. A detailed project description can be found in Appendix S of the Regional Wet Weather Management Plan (RWWMP) Framework.

**PROJECT JUSTIFICATION**

As part of HRSD's Integrated Plan, a program of High Priority RWWMP Projects (HPP) will be constructed through 2030. These projects were selected based on their ability to provide the greatest environmental and human health benefits. Further, this \$200+ million investment will significantly reduce sanitary sewer overflow (SSO) volume at the 5-year level of service by 47 percent.

**FUNDING TYPE**

Funding Type: Clean Water Proposed

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Sam McAdoo  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	07/01/2022
PER	07/01/2022
Design Delay	01/01/2023
Design	01/01/2023
Bid Delay	06/01/2024
PreConstruction	06/01/2024
Construction	09/01/2024
Closeout	01/01/2026

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 5</b>
PrePlanning	\$0
PER	\$455,046
Design	\$1,170,089
PreConstruction	\$195,049
Construction	\$13,007,597
Closeout	\$0
<b>Est. Program Cost</b>	<b>\$14,827,781</b>
Contingency Budget	\$3,251,899
<b>Est. Project Costs</b>	<b>\$18,079,680</b>




**BHO 15802**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



## BHO 15802

### Claremont Pump Station Upgrade (BH-HPP-01B)

**CIP Location**

Hampton



System: Boat Harbor  
Type: Pump Stations

Driver Category: I&I Abatement-IP/RWWMP  
Project Status: Proposed  
Regulatory: Integrated Plan-HPP

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$10,938	\$0	\$0	\$0	\$0	\$535	\$751	\$6,265	\$3,387	\$0	\$0	\$0

**PROJECT DESCRIPTION**

Claremont Pump Station Upgrade (NS-PS-208). A detailed project description can be found in Appendix S of the Regional Wet Weather Management Plan (RWWMP) Framework.

**PROJECT JUSTIFICATION**

As part of HRSD's Integrated Plan, a program of High Priority RWWMP Projects (HPP) will be constructed through 2030. These projects were selected based on their ability to provide the greatest environmental and human health benefits. Further, this \$200+ million investment will significantly reduce sanitary sewer overflow (SSO) volume at the 5-year level of service by 47 percent.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Sam McAdoo  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	10/01/2023
PER	10/01/2023
Design Delay	03/01/2024
Design	03/01/2024
Bid Delay	05/01/2025
PreConstruction	05/01/2025
Construction	08/01/2025
Closeout	01/01/2027

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 5</b>
PrePlanning	\$0
PER	\$279,746
Design	\$895,127
PreConstruction	\$167,868
Construction	\$9,595,261
Closeout	\$0
<b>Est. Program Cost</b>	<b>\$10,938,002</b>
<b>Contingency Budget</b>	<b>\$2,398,815</b>
<b>Est. Project Costs</b>	<b>\$13,336,817</b>




**BHO 15803**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



**BHO 15803**

**Chesapeake Avenue Interceptor  
Improvements (BH-HPP-01C)**

N  
W E  
S

**CIP Location**

Hampton



System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-IP/RWWMP  
Project Status: Proposed  
Regulatory: Integrated Plan-HPP

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$14,776	\$0	\$0	\$0	\$0	\$0	\$815	\$2,438	\$8,642	\$2,881	\$0	\$0

**PROJECT DESCRIPTION**

Upgrade 6,490 linear feet (LF) to 42-inch gravity main (GM); Upgrade 2,180 LF of 24-inch GM to 36-inch GM; Upgrade 70 LF of 42-inch inverted siphon along Chesapeake Avenue upstream of NS-PS-208; Upgrade 70 LF of 42-inch inverted siphon along Chesapeake Avenue upstream of NS-PS-208. A detailed project description can be found in Appendix S of the Regional Wet Weather Management Plan (RWWMP) Framework.

**PROJECT JUSTIFICATION**

As part of HRSD's Integrated Plan, a program of High Priority RWWMP Projects (HPP) will be constructed through 2030. These projects were selected based on their ability to provide the greatest environmental and human health benefits. Further, this \$200+ million investment will significantly reduce sanitary sewer overflow (SSO) volume at the 5-year level of service by 47 percent.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**


Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Sam McAdoo  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	07/01/2024
PER	07/01/2024
Design Delay	03/01/2025
Design	03/01/2025
Bid Delay	03/01/2026
PreConstruction	03/01/2026
Construction	05/01/2026
Closeout	11/01/2027

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 5</b>
PrePlanning	\$0
PER	\$440,285
Design	\$1,123,872
PreConstruction	\$248,901
Construction	\$12,962,805
Closeout	\$0
<b>Est. Program Cost</b>	<b>\$14,775,863</b>
<b>Contingency Budget</b>	<b>\$3,240,701</b>
<b>Est. Project Costs</b>	<b>\$18,016,564</b>




**BHO15900**

- Project Interceptor Line
- Project Interceptor Point
- Project Pump Station Point
- Project Area

**Legend**

- CIP Interceptor Point
- CIP Pump Station Point
- CIP Interceptor Line
- CIP Abandonment
- CIP Project Area
- HRSD Interceptor Force Main
- HRSD Interceptor Gravity Main
- HRSD Treatment Plant
- HRSD Pressure Reducing Station
- HRSD Pump Station



# BHO 15900

## Bloxoms Corner Force Main Replacement



**CIP Location**



Hampton



System: Boat Harbor  
Type: Pipelines

Driver Category: I&I Abatement-Rehabilitation Plan  
Project Status: Proposed  
Regulatory: Rehab Plan Phase Two

Prog Cost	Exp to Previous Year	FY21	FY22	FY23	FY24	FY25	FY26	FY27	FY28	FY29	FY30
\$2,868	\$108	\$182	\$778	\$1,800	\$0	\$0	\$0	\$0	\$0	\$0	\$0

**PROJECT DESCRIPTION**

This project will address 6,100 linear feet of 8-inch Cast Iron Pipe from Bloxom's Corner Pump Station to the gravity discharge at MH-NG-094-1264.

**PROJECT JUSTIFICATION**

Disproportionate force main failure history indicates material risk of failure.

**FUNDING TYPE**

Funding Type: Revenue Bond

**CONTACTS**

Contacts-Requesting Dept: Operations-Interceptors  
Contacts-Dept Contacts: Eddie Abisaab  
Contacts-Managing Dept: Engineering

**PROPOSED SCHEDULE START DATE**

PrePlanning	09/01/2019
PER	05/01/2020
Design Delay	09/01/2020
Design	09/01/2020
Bid Delay	11/01/2021
PreConstruction	11/01/2021
Construction	03/01/2022
Closeout	05/01/2023

**COST ESTIMATE**

<b>Cost Estimate Class:</b>	<b>Class 5</b>
PrePlanning	\$62,824
PER	\$90,434
Design	\$192,095
PreConstruction	\$5,310
Construction	\$2,511,868
Closeout	\$5,310
<b>Est. Program Cost</b>	<b>\$2,867,840</b>
Contingency Budget	\$627,967
<b>Est. Project Costs</b>	<b>\$3,495,808</b>